

PUBLIC WORKS PROJECT LISTING 2023-2027

	PROJECT & SCOPE	START	ACTION ITEMS	TASK	COMMENTS	COMPLETED	END
1)	Intersection Stabilization - stabilize 4 busy intersections within the RM with a stabilizing product or other method.	Spring 2023	1. Source appropriate material 2. Test material and clay content 3. When appropriate method or material has been found, determine project timelines and costs.	Travis	Currently, researching products and waiting to see how the Township Road 234 improvements work and the Sorensen Beach reclaimed asphalt project		Fall 2024
2)	Backroad Maintenance - Clear backroads, that are not regularly maintained or a part of the regular grading service, to allow access to fields and move equipment. Timeline - ongoing mostly late summer early fall.	Sept, 2023	1. Determine roads for brush removal 2. Using RM equipment clear brush and other obstacles from designated roads. 3. Reseed any areas that require it.	Travis	Significant work was completed during the winter. The rest will be finished this fall.		Nov-23
3)	Township RD 234 Road Improvement - Improve the Uhl's Bay road west from Highway 220 to the 4 way stop. This road was identified in the road assessment as needing improvements.	May-23	1. Consult with Council and determine best method/product. 2. Pull shoulders and narrow road top. 3. Incorporate gravel, clay, water and product into road materials. 4. Apply reworked road material to roadway. 5. Compact and grade surface. 6. Complete reporting for CCBF (Gas Tax)	Travis Camille		PROJECT COMPLETED	Jun-23

PUBLIC WORKS PROJECT LISTING 2023-2027

4)	Radar Sign Trailer - The RM purchased a radar display sign to encourage traffic to slow down on slower speed roads. The RM needed to fabriate a trailer to make one sign portable.	Jun-23	1. Design trailer. 2. Source materials. 3. Determine costs of materials 4. Build trailer.	Travis		PROJECT COMPLETED	
5)	Heritage Valley Drainage/Culvert - A culvert was damaged by SaskEnergy when performing work. Repairs will be performed on the adjacent ditches. Timeline - June.	Jul-23	1. Consult with SaskEnergy regarding timeline. 2. Work with SaskEnergy to change all culverts damaged by gasline installation. 3. Perform repairs on adjavcent ditches.	Travis	SaskEnergy has almost completed its work as of July 24th. PW will start their work next week.	PROJECT COMPLETED	Aug-23
6)	Township 222 Revitalization - Brush removal project to clear the road east of highway 322 at a farmer's request.	Aug-23	1. Remove brush from road allowance. 2. Remove any fencing that inhibits the project. 4. Construct elevated road through 2 ravines with 3' grade and 20' top. 5. Install suitable culverts in the ravines. 6. Shape road surface with 20' top and ditching the entire mile. 7. Replace any fencing removed for the project. 8. Perform work in such a way that the road can then be maintained by a mower or farmed by adjacent land owners.	Travis	Brush removal has been in progress for approx 3 weeks.		Oct-23

PUBLIC WORKS PROJECT LISTING 2023-2027

7)	Fox's Point Road Widening - Widen road and repair section of road near Fox's Point that was previously flooded. Dirt material will be sourced from 1 mile east on road allowance.	Sep-23	1. Investigate Scope 2. Determine if outside contractor is required. 3. Remove bails from existing road slope adjacent to the slough. 4. Widen road width to be consistent with existing road surfaces to the east and west of chosen site. 5. Rebuild road fore-slope and install culvert in appropriate location.	Travis	Work can and will be performed by an RM public works crew.	X X	Sep-23
8)	Boat Launch Repairs - Shore Acres - Repair boat launch road.	Jul-23	1. Add rock to side of road where it has been washed out.	Travis		PROJECT COMPLETED	Jul-23
9)	Rock Removal - Removal of protruding rocks from driving surfaces.Roads include: - Finish 731 east of Strasbourg. - Grid road south of Strasbourg to highway 220. - Grid road north of Bulyea up to 731 eat of Strasabourg. - Access roads off of 731 leading to Colling wood and the bible camp.	May-23	1. Choose roads for rock removal work. 2. Complete map of chosen roads. 3. Remove rocks from roads. 4. Refill and compact holes left from rock removal.			Project Ongoing	Jun-23
10)	Pavement Repairs Strasbourg East 731 - Repair the pavement surface on the road east of Strasbourg.	Jul-23	1. Investigate scope and costs of pavement improvements needed for 731 east. 2. Source Contractor for Project 3. Set project costs and timelines	Travis/C amille	PW started crack sealing July 24, 2023	Project Completed	End of August 2023

PUBLIC WORKS PROJECT LISTING 2023-2027

11)	Boat Launch Decommission - Council has decided that it would be more cost-effective to have only one boat launch for the hamlets of Clearview and Shoreline. One boat launch will have to be decommissioned and one repaired/improved.	May-24	1. Consult hamlet residents and boards 2. Determine scope of project, costs and timelines	Camille Travis/C amille	July 18th, Council passed a resolution to close Clearview and improve Shoreline's boat launch.		Jul-24
12)	Boat Launch Improvements - Council has decided that it would be more cost-effective to have only one boat launch for the hamlets of Clearview and Shoreline. One boat launch will have to be decommissioned and one repaired/improved.	May-24	1. Decide on upgrade/repairs for boat launch and scope of those tasks. 2. Determine available parking and possible parking improvements 3. Investigate costs for proposed improvements for parking and boat launch 4. Find recreation infrastructure funding grants 5. Set project costs and timelines. 6. Determine if outside source is required for project.	Travis Camille	July 18th, Council decided to improve the boat launch at Shoreline because it has more potential to increase available parking.		Aug-24
13)	Reenforce north side of 731 West - Road was compromised during flooding years. A more permanent solution is needed.	May-24	1. Investigate scope of project and timelines. 2. Improve road fore-slope of the road adjacent to slough. 3. Re-install rock/rip rap to protect roadway.	Travis	Will possibly need contractor for project.		May-24
14)	Backroad Maintenance - Clear backroads, that are not regularly maintained or a part of the regular grading service, to allow access to fields and move equipment. Timeline - ongoing mostly late summer early fall.	May-24	1. Determine roads for brush removal 2. Using RM equipment clear brush and other obstacles from designated roads. 3. Reseed any areas that require it.	Travis			Ongoing

PUBLIC WORKS PROJECT LISTING 2023-2027

15)	Bulyea House Removal - The RM acquired the house and adjacent lots to the RM administration building. The house needs to be demolished or removed due to poor condition.	May-24					
16)	RM Shop - The RM does not have a shop to operate out of. We currently rent a building in RM 219. More reserves are required prior planning or building.	Fall 2027					
17)	Clay-capping 731 West	Summer 2025 Summer 2027	1. Choose section of road 2. Investigate costs and timelines 3. Set costs and timelines 4. Source contractor 5. Choose contractor	Travis/C amille			Fall 2027 Fall 2028